



# SMCCCD - Cañada College

## Appendix I: Sidewalks

### Access Compliance Survey Report

DRAFT



# Table of Contents

## I. Cover & Table of Contents

- i. Report Navigation and Legend, Abbreviations
- ii. Master Street List
- iii. Cost Summary

## II. Survey Data - Sidewalks



## NAVIGATION & LEGEND

# NAVIGATION

Cañada College										Access Compliance Survey Report - Sidewalks			Route 17	
Funding Source: <b>TBD</b>										Year to be Completed <b>TBD</b>				
Direction Traveled	Run ID	Route	Start of Route			End of Route			Priority					
<b>SW</b>	<b>1906050832</b>	<b>ROUTE 17</b>	<b>BUILDING 8</b>			<b>BUILDING 8</b>			<b>TBD</b>					
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes		Sidewalk Width	Qty	Unit	Cost	Total					
1352786	0.9 to 3.3 feet	Cross Slope (PAR)	4-5%		20 ft	48	SF	\$120	\$5,760					
1352787	4.8 to 9.3 feet	Cross Slope (PAR)	3-4%		20 ft	90	SF	\$120	\$10,800					
1352788	9.6 to 11.7 feet	Cross Slope (PAR)	3-4%		20 ft	42	SF	\$120	\$5,040					
1352789	13.3 to 17.5 feet	Cross Slope (PAR)	4-5%		20 ft	84	SF	\$120	\$10,080					
1352790	18.4 to 22.6 feet	Cross Slope (PAR)	3-4%		20 ft	84	SF	\$120	\$10,080					
1352791	23.4 to 24.4 feet	Cross Slope (PAR)	3-4%		20 ft	20	SF	\$120	\$2,400					
1352792	24.5 to 27.2 feet	Cross Slope (PAR)	3-4%		20 ft	54	SF	\$120	\$6,480					
1352793	27.3 to 30.7 feet	Cross Slope (PAR)	3-4%		20 ft	68	SF	\$120	\$8,160					
1352794	30.8 to 33.1 feet	Cross Slope (PAR)	4-5%		20 ft	46	SF	\$120	\$5,520					
<b>TOTAL COST FOR: SW</b>								<i>dir. of</i> <b>ROUTE 17</b>		<i>Starting at:</i> <b>BUILDING 8</b>		<b>\$64,320.00</b>		

- Direction of Travel:** Corresponds to the side of the street surveyed:  
- N, S, E and W.
- Dist. from Start:** The location of the identified barrier, measured in feet from the starting building or route.
- Route:** Name of arterial/primary route for which barriers are being surveyed.
- Barrier Type:** Type of barrier recorded.
- Start of Route:** Name of the starting building from which barrier locations are being measured.
- Measurement:** Existing condition/dimension.
- Sidewalk Width:** Width of the sidewalk measured in feet.
- Qty:** Number of solutions required.
- End of Route:** Name of the ending building from which barrier locations are being measured.
- Unit:** Unit of measurement used to compute estimate. LF=linear feet; SF=square feet; JOB=lump sum; REF=reference
- Cost:** Estimated cost of specific solution per one unit (the final cost of barrier removal may exceed this estimate based on the year of mitigation, design approach, and chosen method of mitigation).
- Total:** Total estimated cost for removing identified barrier (multiplied Qty by Cost).
- Priority:** Priority number assigned to specific barrier based on prioritization criteria which include: expected frequency of use and severity of the barrier. Measured on a scale of 0 to 200, with 200 being the highest priority and 0 being the least.

## LEGEND ABBREVIATIONS

ADA	Americans with Disabilities Act
ADAAG	ADA Accessibility Guidelines
E	East
Fig.	Figure
JOB	per one job (lump sum)
lbs.	Pounds
LF	Linear foot
MUTCD	Manual on Uniform Traffic Control Devices
N	North
NE	Northeast
NW	Northwest
POT	Path of travel
PROW	Public Right-of-Way
PROWAG	Public Right-of-Way Accessible Guidelines
Qty	Quantity
REF	Reference; Provided in locations with overlapping issue; indicates no addition cost required for mitigation
S	South
SE	Southeast
SF	Square foot
SW	Southwest
TBD	To be determined
W	West



## MASTER ROUTES LIST

	<i>Total Cost for Street:</i>
Street: <b>ROUTE 12</b>	<b>\$171,900.00</b>
Street: <b>ROUTE 13</b>	<b>\$113,880.00</b>
Street: <b>ROUTE 16</b>	<b>\$112,200.00</b>
Street: <b>ROUTE 17</b>	<b>\$64,320.00</b>
Street: <b>ROUTE 18</b>	<b>\$8,160.00</b>
Street: <b>ROUTE 21</b>	<b>\$62,472.00</b>
Street: <b>ROUTE 24</b>	<b>\$27,900.00</b>
Street: <b>ROUTE 25</b>	<b>\$4,500.00</b>
Street: <b>ROUTE 26</b>	<b>\$24,480.00</b>
Street: <b>ROUTE 27</b>	<b>\$16,320.00</b>
Street: <b>ROUTE 29</b>	<b>\$65,040.00</b>
Street: <b>ROUTE 30</b>	<b>\$49,680.00</b>
Street: <b>ROUTE 34</b>	<b>\$1,440.00</b>
Street: <b>ROUTE 35</b>	<b>\$85,380.00</b>
Street: <b>ROUTE 40</b>	<b>\$26,940.00</b>
Street: <b>ROUTE 41</b>	<b>\$4,800.00</b>
Street: <b>ROUTE 52</b>	<b>\$28,035.00</b>
Street: <b>ROUTE 53</b>	<b>\$2,700.00</b>
Street: <b>ROUTE 57</b>	<b>\$4,500.00</b>
Street: <b>ROUTE 58</b>	<b>\$24,270.00</b>
Street: <b>ROUTE 59</b>	<b>\$5,640.00</b>
Street: <b>ROUTE 60</b>	<b>\$62,100.00</b>
Street: <b>ROUTE 61</b>	<b>\$14,640.00</b>
Street: <b>ROUTE 62</b>	<b>\$285,360.00</b>
Street: <b>ROUTE 63</b>	<b>\$10,500.00</b>
Street: <b>ROUTE 64</b>	<b>\$49,680.00</b>
Street: <b>ROUTE 65</b>	<b>\$11,322.00</b>
Street: <b>ROUTE 8</b>	<b>\$94,020.00</b>
Street: <b>ROUTE 9</b>	<b>\$55,920.00</b>
<b>Total Cost for College Sidewalks:</b>	<b>\$1,488,099.00</b>



## COST SUMMARY



<b>ROUTE 12</b>				<b>Total Cost for Route:</b>	<b>\$171,900.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 12	BUILDING 5	LOT 8	NW		\$171,900.00
<b>ROUTE 13</b>				<b>Total Cost for Route:</b>	<b>\$113,880.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 13	BUILDING 8	LOT 4	SW		\$113,880.00
<b>ROUTE 16</b>				<b>Total Cost for Route:</b>	<b>\$112,200.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 16	BUILDING 5	BUILDING 8	NW		\$112,200.00
<b>ROUTE 17</b>				<b>Total Cost for Route:</b>	<b>\$64,320.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 17	BUILDING 8	BUILDING 8	SW		\$64,320.00
<b>ROUTE 18</b>				<b>Total Cost for Route:</b>	<b>\$8,160.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 18	BUILDING 8	BUILDING 8	SW		\$8,160.00
<b>ROUTE 21</b>				<b>Total Cost for Route:</b>	<b>\$62,472.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 21	BUILDING 3	BUILDING 8	SW		\$62,472.00
<b>ROUTE 24</b>				<b>Total Cost for Route:</b>	<b>\$27,900.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 24	BUILDING 9	BUILDING 13	SW		\$27,900.00
<b>ROUTE 25</b>				<b>Total Cost for Route:</b>	<b>\$4,500.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 25	BUILDING 13	BUILDING 9	E		\$4,500.00
<b>ROUTE 26</b>				<b>Total Cost for Route:</b>	<b>\$24,480.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 26	BUILDING 9	BUILDING 9	E		\$24,480.00
<b>ROUTE 27</b>				<b>Total Cost for Route:</b>	<b>\$16,320.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 27	BUILDING 17	BUILDING 17	E/S		\$16,320.00
<b>ROUTE 29</b>				<b>Total Cost for Route:</b>	<b>\$65,040.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 29	BUILDING 18	BUILDING 9	S		\$65,040.00
<b>ROUTE 30</b>				<b>Total Cost for Route:</b>	<b>\$49,680.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 30	BUILDING 16	BUILDING 16	W		\$49,680.00
<b>ROUTE 34</b>				<b>Total Cost for Route:</b>	<b>\$1,440.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 34	BUILDING 17	BUILDING 8	W		\$1,440.00
<b>ROUTE 35</b>				<b>Total Cost for Route:</b>	<b>\$85,380.00</b>
Route	Starting Route	Ending Route	Direction Traveled		
ROUTE 35	LOT 10	LOT 8	NE		\$85,380.00
<b>ROUTE 40</b>				<b>Total Cost for Route:</b>	<b>\$26,940.00</b>
Route	Starting Route	Ending Route	Direction Traveled		

<b>ROUTE 40</b>	<b>LOT 1</b>	<b>BUILDING 9</b>	<b>W</b>	<b>\$26,940.00</b>
<b>ROUTE 41</b>			<b>Total Cost for Route:</b>	<b>\$4,800.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 41</b>	<b>LOT 1</b>	<b>BUILDING 9</b>	<b>W</b>	<b>\$4,800.00</b>
<b>ROUTE 52</b>			<b>Total Cost for Route:</b>	<b>\$28,035.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 52</b>	<b>LOT 1</b>	<b>LOT 1</b>	<b>W</b>	<b>\$28,035.00</b>
<b>ROUTE 53</b>			<b>Total Cost for Route:</b>	<b>\$2,700.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 53</b>	<b>LOT 1</b>	<b>BUILDING 9</b>	<b>W</b>	<b>\$2,700.00</b>
<b>ROUTE 57</b>			<b>Total Cost for Route:</b>	<b>\$4,500.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 57</b>	<b>BUILDING 3</b>	<b>BUILDING 2</b>	<b>W</b>	<b>\$4,500.00</b>
<b>ROUTE 58</b>			<b>Total Cost for Route:</b>	<b>\$24,270.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 58</b>	<b>BUILDING 2</b>	<b>LOT 4</b>	<b>S</b>	<b>\$24,270.00</b>
<b>ROUTE 59</b>			<b>Total Cost for Route:</b>	<b>\$5,640.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 59</b>	<b>BUILDING 3</b>	<b>BUILDING 3</b>	<b>N</b>	<b>\$5,640.00</b>
<b>ROUTE 60</b>			<b>Total Cost for Route:</b>	<b>\$62,100.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 60</b>	<b>BUILDING 3</b>	<b>BUILDING 3</b>	<b>E</b>	<b>\$62,100.00</b>
<b>ROUTE 61</b>			<b>Total Cost for Route:</b>	<b>\$14,640.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 61</b>	<b>BUILDING 3</b>	<b>BUILDING 3</b>	<b>SE</b>	<b>\$14,640.00</b>
<b>ROUTE 62</b>			<b>Total Cost for Route:</b>	<b>\$285,360.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 62</b>	<b>BUILDING 18</b>	<b>LOT 9</b>	<b>W /</b>	<b>\$285,360.00</b>
<b>ROUTE 63</b>			<b>Total Cost for Route:</b>	<b>\$10,500.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 63</b>	<b>BUILDING 22</b>	<b>BUILDING 22</b>	<b>E</b>	<b>\$10,500.00</b>
<b>ROUTE 64</b>			<b>Total Cost for Route:</b>	<b>\$49,680.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 64</b>	<b>BUILDING 22</b>	<b>BUILDING 17</b>	<b>S</b>	<b>\$49,680.00</b>
<b>ROUTE 65</b>			<b>Total Cost for Route:</b>	<b>\$11,322.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 65</b>	<b>BUILDING 18</b>	<b>BUILDING 18</b>	<b>W</b>	<b>\$11,322.00</b>
<b>ROUTE 8</b>			<b>Total Cost for Route:</b>	<b>\$94,020.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 8</b>	<b>CAMPUS CIR</b>	<b>BUILDING 3</b>	<b>NE /</b>	<b>\$94,020.00</b>
<b>ROUTE 9</b>			<b>Total Cost for Route:</b>	<b>\$55,920.00</b>
Route	Starting Route	Ending Route	Direction Traveled	
<b>ROUTE 9</b>	<b>BUILDING 9</b>	<b>BUILDING 16</b>	<b>N</b>	<b>\$55,920.00</b>


**Total Cost for College Sidewalks: \$1,488,099.00**



## SURVEY DATA



Cañada Path of Travel Routes



Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Funding Source: **TBD**Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route					Priority
<b>NW</b>	<b>1906050848</b>	<b>ROUTE 12</b>	<b>BUILDING 5</b>	<b>LOT 8</b>					<b>117.25</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1352842	0.0 to 1.3 feet	Cross Slope (PAR)	2-3%	20 ft	26	SF	\$120	<b>\$3,120</b>	
1352843	1.4 to 3.4 feet	Cross Slope (PAR)	2-3%	20 ft	40	SF	\$120	<b>\$4,800</b>	
1352839	3.3 to 4.3 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1352844	3.8 to 10.7 feet	Cross Slope (PAR)	2-3%	20 ft	138	SF	\$120	<b>\$16,560</b>	
1352840	11.6 to 14.8 feet	<b>Vertical Change</b>	.3	20 ft	64	LF	\$75	<b>\$4,800</b>	
1352845	13.3 to 14.7 feet	Cross Slope (PAR)	2-3%	20 ft	28	SF	\$120	<b>\$3,360</b>	
1352846	15.0 to 37.4 feet	Cross Slope (PAR)	2-3%	20 ft	448	SF	\$120	<b>\$53,760</b>	
1352841	40.4 to 41.4 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1352847	97.0 to 98.8 feet	Cross Slope (PAR)	2-3%	20 ft	36	SF	\$120	<b>\$4,320</b>	
1352848	98.9 to 101.3 feet	Cross Slope (PAR)	2-3%	20 ft	48	SF	\$120	<b>\$5,760</b>	
1352849	101.5 to 103.0 feet	Cross Slope (PAR)	2-3%	20 ft	30	SF	\$120	<b>\$3,600</b>	
1352850	126.4 to 128.3 feet	Cross Slope (PAR)	2-3%	20 ft	38	SF	\$120	<b>\$4,560</b>	
1352851	299.9 to 301.4 feet	Cross Slope (PAR)	2-3%	20 ft	30	SF	\$120	<b>\$3,600</b>	
1352852	323.4 to 324.7 feet	Cross Slope (PAR)	2-3%	20 ft	26	SF	\$120	<b>\$3,120</b>	
1352853	363.8 to 365.8 feet	Cross Slope (PAR)	2-3%	20 ft	40	SF	\$120	<b>\$4,800</b>	
1352854	436.6 to 441.3 feet	Cross Slope (PAR)	2-3%	20 ft	94	SF	\$120	<b>\$11,280</b>	
1352855	453.5 to 455.1 feet	Cross Slope (PAR)	2-3%	20 ft	32	SF	\$120	<b>\$3,840</b>	
1352856	578.7 to 580.8 feet	Cross Slope (PAR)	2-3%	20 ft	42	SF	\$120	<b>\$5,040</b>	
1352857	631.9 to 633.2 feet	Cross Slope (PAR)	2-3%	20 ft	26	SF	\$120	<b>\$3,120</b>	
1352858	636.9 to 638.6 feet	Cross Slope (PAR)	2-3%	20 ft	34	SF	\$120	<b>\$4,080</b>	
1352859	675.3 to 681.1 feet	Cross Slope (PAR)	2-3%	20 ft	116	SF	\$120	<b>\$13,920</b>	
1352860	707.8 to 710.8 feet	Cross Slope (PAR)	2-3%	20 ft	60	SF	\$120	<b>\$7,200</b>	
1352861	812.2 to 814.6 feet	Running Slope	5-6%	20 ft	48	SF	\$120	<b>\$5,760</b>	
1352795	10.6 to 11.6 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1352799	20.7 to 22.1 feet	Cross Slope (PAR)	2-3%	20 ft	28	SF	\$120	<b>\$3,360</b>	
1352800	22.6 to 25.3 feet	Cross Slope (PAR)	3-4%	20 ft	54	SF	\$120	<b>\$6,480</b>	
1352801	25.6 to 26.8 feet	Cross Slope (PAR)	3-4%	20 ft	24	SF	\$120	<b>\$2,880</b>	
1352802	26.8 to 29.1 feet	Cross Slope (PAR)	2-3%	20 ft	46	SF	\$120	<b>\$5,520</b>	

Funding Source: **TBD**Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route	Year to be Completed <b>TBD</b>					Priority
<b>SW</b>	<b>1906050839</b>	<b>ROUTE 13</b>	<b>BUILDING 8</b>	<b>LOT 4</b>						<b>123.5</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total		
1352803	36.5 to 40.2 feet	Cross Slope (PAR)	2-3%	20 ft	74	SF	\$120	<b>\$8,880</b>		
1352804	41.3 to 43.0 feet	Cross Slope (PAR)	4-5%	20 ft	34	SF	\$120	<b>\$4,080</b>		
1352805	43.1 to 47.9 feet	Cross Slope (PAR)	4-5%	20 ft	96	SF	\$120	<b>\$11,520</b>		
1352806	49.8 to 52.3 feet	Cross Slope (PAR)	6-7%	20 ft	50	SF	\$120	<b>\$6,000</b>		
1352807	53.8 to 57.1 feet	Cross Slope (PAR)	5-6%	20 ft	66	SF	\$120	<b>\$7,920</b>		
1352808	57.8 to 60.4 feet	Cross Slope (PAR)	4-5%	20 ft	52	SF	\$120	<b>\$6,240</b>		
1352809	60.6 to 65.2 feet	Cross Slope (PAR)	3-4%	20 ft	92	SF	\$120	<b>\$11,040</b>		
1352810	68.3 to 69.3 feet	Cross Slope (PAR)	3-4%	20 ft	20	SF	\$120	<b>\$2,400</b>		
1352811	69.3 to 70.8 feet	Cross Slope (PAR)	2-3%	20 ft	30	SF	\$120	<b>\$3,600</b>		
1352812	71.2 to 73.4 feet	Cross Slope (PAR)	2-3%	20 ft	44	SF	\$120	<b>\$5,280</b>		
1352813	74.7 to 76.1 feet	Cross Slope (PAR)	2-3%	20 ft	28	SF	\$120	<b>\$3,360</b>		
1352796	76.0 to 77.0 feet	<b>Vertical Change</b>	.4	20 ft	20	REF				
1352814	76.2 to 78.0 feet	Cross Slope (PAR)	2-3%	20 ft	36	SF	\$120	<b>\$4,320</b>		
1352815	81.6 to 83.3 feet	Cross Slope (PAR)	2-3%	20 ft	34	SF	\$120	<b>\$4,080</b>		
1352816	83.6 to 88.4 feet	Cross Slope (PAR)	2-3%	20 ft	96	SF	\$120	<b>\$11,520</b>		
1352797	86.2 to 87.2 feet	<b>Vertical Change</b>	.4	20 ft	20	REF				
1352817	90.0 to 91.0 feet	Cross Slope (PAR)	2-3%	20 ft	20	SF	\$120	<b>\$2,400</b>		
1352798	118.8 to 119.8 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>		
1352837	4.4 to 6.2 feet	Running Slope	6-7%	20 ft	36	SF	\$120	<b>\$4,320</b>		
1352838	6.6 to 8.3 feet	Running Slope	5-6%	20 ft	34	SF	\$120	<b>\$4,080</b>		
1352821	11.8 to 14.3 feet	Cross Slope (PAR)	2-3%	20 ft	50	SF	\$120	<b>\$6,000</b>		
1352822	15.5 to 20.4 feet	Cross Slope (PAR)	5-6%	20 ft	98	SF	\$120	<b>\$11,760</b>		
1352823	44.7 to 46.5 feet	Cross Slope (PAR)	2-3%	20 ft	36	SF	\$120	<b>\$4,320</b>		
1352824	47.3 to 48.6 feet	Cross Slope (PAR)	2-3%	20 ft	26	SF	\$120	<b>\$3,120</b>		
1352825	64.2 to 65.7 feet	Cross Slope (PAR)	2-3%	20 ft	30	SF	\$120	<b>\$3,600</b>		
1352826	66.4 to 68.3 feet	Cross Slope (PAR)	3-4%	20 ft	38	SF	\$120	<b>\$4,560</b>		
1352827	68.4 to 70.2 feet	Cross Slope (PAR)	3-4%	20 ft	36	SF	\$120	<b>\$4,320</b>		
1352828	71.1 to 73.4 feet	Cross Slope (PAR)	5-6%	20 ft	46	SF	\$120	<b>\$5,520</b>		

Funding Source: **TBD**

Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route	Year to be Completed				Priority
<b>NW</b>	<b>1906050841</b>	<b>ROUTE 16</b>	<b>BUILDING 5</b>	<b>BUILDING 8</b>					<b>124.75</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1352818	73.3 to 74.3 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1352829	74.4 to 76.3 feet	Cross Slope (PAR)	5-6%	20 ft	38	SF	\$120	<b>\$4,560</b>	
1352830	77.6 to 78.7 feet	Cross Slope (PAR)	4-5%	20 ft	22	SF	\$120	<b>\$2,640</b>	
1352831	79.6 to 80.7 feet	Cross Slope (PAR)	3-4%	20 ft	22	SF	\$120	<b>\$2,640</b>	
1352819	116.5 to 117.5 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1352820	149.9 to 150.9 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1352832	152.6 to 155.0 feet	Cross Slope (PAR)	2-3%	20 ft	48	SF	\$120	<b>\$5,760</b>	
1352833	155.8 to 156.8 feet	Cross Slope (PAR)	3-4%	20 ft	20	SF	\$120	<b>\$2,400</b>	
1352834	156.9 to 169.0 feet	Cross Slope (PAR)	3-4%	20 ft	242	SF	\$120	<b>\$29,040</b>	
1352835	170.5 to 172.3 feet	Cross Slope (PAR)	3-4%	20 ft	36	SF	\$120	<b>\$4,320</b>	
1352836	172.3 to 174.9 feet	Cross Slope (PAR)	2-3%	20 ft	52	SF	\$120	<b>\$6,240</b>	
1352786	0.9 to 3.3 feet	Cross Slope (PAR)	4-5%	20 ft	48	SF	\$120	<b>\$5,760</b>	
1352787	4.8 to 9.3 feet	Cross Slope (PAR)	3-4%	20 ft	90	SF	\$120	<b>\$10,800</b>	
1352788	9.6 to 11.7 feet	Cross Slope (PAR)	3-4%	20 ft	42	SF	\$120	<b>\$5,040</b>	
1352789	13.3 to 17.5 feet	Cross Slope (PAR)	4-5%	20 ft	84	SF	\$120	<b>\$10,080</b>	
1352790	18.4 to 22.6 feet	Cross Slope (PAR)	3-4%	20 ft	84	SF	\$120	<b>\$10,080</b>	
1352791	23.4 to 24.4 feet	Cross Slope (PAR)	3-4%	20 ft	20	SF	\$120	<b>\$2,400</b>	
1352792	24.5 to 27.2 feet	Cross Slope (PAR)	3-4%	20 ft	54	SF	\$120	<b>\$6,480</b>	
1352793	27.3 to 30.7 feet	Cross Slope (PAR)	3-4%	20 ft	68	SF	\$120	<b>\$8,160</b>	
1352794	30.8 to 33.1 feet	Cross Slope (PAR)	4-5%	20 ft	46	SF	\$120	<b>\$5,520</b>	
1352782	15.1 to 19.7 feet	Cross Slope (PAR)	2-3%	5 ft	23	SF	\$120	<b>\$2,760</b>	
1352776	16.3 to 17.3 feet	<b>Vertical Change</b>	.3	5 ft	5	REF			
1352777	22.5 to 23.5 feet	<b>Vertical Change</b>	.3	5 ft	5	LF	\$75	<b>\$375</b>	
1352778	28.7 to 29.7 feet	<b>Vertical Change</b>	.3	5 ft	5	LF	\$75	<b>\$375</b>	
1352783	34.0 to 35.5 feet	Cross Slope (PAR)	2-3%	5 ft	8	SF	\$120	<b>\$900</b>	
1352779	34.9 to 35.9 feet	<b>Vertical Change</b>	.3	5 ft	5	REF			
1352784	42.5 to 44.4 feet	Cross Slope (PAR)	2-3%	5 ft	10	SF	\$120	<b>\$1,140</b>	
1352780	47.2 to 48.2 feet	<b>Vertical Change</b>	.3	5 ft	5	LF	\$75	<b>\$375</b>	

Funding Source: **TBD**Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route					Priority
<b>SW</b>	<b>1906050827</b>	<b>ROUTE 18</b>	<b>BUILDING 8</b>	<b>BUILDING 8</b>					<b>116.25</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1352781	53.3 to 54.3 feet	<b>Vertical Change</b>	.4	5 ft	5	LF	\$75	<b>\$375</b>	
1352785	59.3 to 62.4 feet	Running Slope	5-6%	5 ft	16	SF	\$120	<b>\$1,860</b>	
1352757	0.0 to 1.8 feet	Cross Slope (PAR)	2-3%	8 ft	14	SF	\$120	<b>\$1,728</b>	
1352751	6.7 to 7.7 feet	<b>Vertical Change</b>	.3	8 ft	8	LF	\$75	<b>\$600</b>	
1352767	10.3 to 11.9 feet	Running Slope	5-6%	8 ft	13	SF	\$120	<b>\$1,536</b>	
1352758	16.8 to 21.3 feet	Cross Slope (PAR)	2-3%	8 ft	36	SF	\$120	<b>\$4,320</b>	
1352768	32.4 to 37.0 feet	Running Slope	5-6%	8 ft	37	SF	\$120	<b>\$4,416</b>	
1352752	41.0 to 42.0 feet	<b>Vertical Change</b>	.4	8 ft	8	LF	\$75	<b>\$600</b>	
1352769	43.3 to 44.3 feet	Running Slope	5-6%	8 ft	8	SF	\$120	<b>\$960</b>	
1352770	49.6 to 50.9 feet	Running Slope	5-6%	8 ft	10	SF	\$120	<b>\$1,248</b>	
1352771	51.3 to 52.5 feet	Running Slope	5-6%	8 ft	10	SF	\$120	<b>\$1,152</b>	
1352753	53.8 to 54.8 feet	<b>Vertical Change</b>	.3	8 ft	8	LF	\$75	<b>\$600</b>	
1352772	56.6 to 59.1 feet	Running Slope	5-6%	8 ft	20	SF	\$120	<b>\$2,400</b>	
1352773	63.3 to 71.8 feet	Running Slope	5-6%	8 ft	68	SF	\$120	<b>\$8,160</b>	
1352759	73.7 to 76.0 feet	Cross Slope (PAR)	2-3%	8 ft	18	SF	\$120	<b>\$2,208</b>	
1352760	76.1 to 77.8 feet	Cross Slope (PAR)	3-4%	8 ft	14	SF	\$120	<b>\$1,632</b>	
1352774	95.8 to 97.0 feet	Running Slope	5-6%	8 ft	10	SF	\$120	<b>\$1,152</b>	
1352775	109.8 to 118.2 feet	Running Slope	5-6%	8 ft	67	SF	\$120	<b>\$8,064</b>	
1352761	114.7 to 116.0 feet	Cross Slope (PAR)	2-3%	8 ft	10	SF	\$120	<b>\$1,248</b>	
1352754	115.3 to 116.3 feet	<b>Vertical Change</b>	.3	8 ft	8	REF			
1352762	116.1 to 118.8 feet	Cross Slope (PAR)	2-3%	8 ft	22	SF	\$120	<b>\$2,592</b>	
1352763	119.0 to 121.6 feet	Cross Slope (PAR)	3-4%	8 ft	21	SF	\$120	<b>\$2,496</b>	
1352764	121.7 to 122.8 feet	Cross Slope (PAR)	3-4%	8 ft	9	SF	\$120	<b>\$1,056</b>	
1352765	122.8 to 124.2 feet	Cross Slope (PAR)	2-3%	8 ft	11	SF	\$120	<b>\$1,344</b>	
1352755	123.5 to 124.5 feet	<b>Vertical Change</b>	.4	8 ft	8	REF			
1352766	134.3 to 147.8 feet	Cross Slope (PAR)	2-3%	8 ft	108	SF	\$120	<b>\$12,960</b>	
1352756	136.0 to 137.0 feet	<b>Vertical Change</b>	.3	8 ft	8	REF			
1353027	41.9 to 42.9 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	



Funding Source: **TBD**Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route					Priority
<b>SW</b>	<b>1906050923</b>	<b>ROUTE 24</b>	<b>BUILDING 9</b>	<b>BUILDING 13</b>					<b>115</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1353028	63.4 to 64.4 feet	<b>Vertical Change</b>	.5	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353029	71.9 to 72.9 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353030	80.4 to 81.4 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353033	118.1 to 119.1 feet	Cross Slope (PAR)	2-3%	20 ft	20	SF	\$120	<b>\$2,400</b>	
1353031	120.6 to 121.6 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1353034	120.6 to 128.1 feet	Cross Slope (PAR)	2-3%	20 ft	150	SF	\$120	<b>\$18,000</b>	
1353032	134.1 to 135.1 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353035	5.8 to 6.8 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353036	53.2 to 54.2 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353037	65.5 to 66.5 feet	<b>Vertical Change</b>	.4	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353038	7.2 to 10.2 feet	<b>Vertical Change</b>	.4	20 ft	60	LF	\$75	<b>\$4,500</b>	
1353039	13.5 to 14.5 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353044	35.4 to 36.7 feet	Cross Slope (PAR)	4-5%	20 ft	26	SF	\$120	<b>\$3,120</b>	
1353040	37.6 to 38.6 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1353045	38.5 to 39.8 feet	Cross Slope (PAR)	3-4%	20 ft	26	SF	\$120	<b>\$3,120</b>	
1353046	40.4 to 41.8 feet	Cross Slope (PAR)	2-3%	20 ft	28	SF	\$120	<b>\$3,360</b>	
1353041	41.5 to 42.5 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1353047	47.6 to 49.9 feet	Cross Slope (PAR)	3-4%	20 ft	46	SF	\$120	<b>\$5,520</b>	
1353042	48.1 to 49.1 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1353048	51.7 to 53.1 feet	Cross Slope (PAR)	2-3%	20 ft	28	SF	\$120	<b>\$3,360</b>	
1353043	52.4 to 53.4 feet	<b>Vertical Change</b>	.4	20 ft	20	REF			
1352999	24.7 to 26.2 feet	Cross Slope (PAR)	2-3%	10 ft	15	SF	\$120	<b>\$1,800</b>	
1353000	27.0 to 31.4 feet	Cross Slope (PAR)	2-3%	10 ft	44	SF	\$120	<b>\$5,280</b>	
1353001	52.6 to 56.6 feet	Cross Slope (PAR)	2-3%	10 ft	40	SF	\$120	<b>\$4,800</b>	
1353002	61.5 to 64.0 feet	Cross Slope (PAR)	2-3%	10 ft	25	SF	\$120	<b>\$3,000</b>	
1353003	0.2 to 1.4 feet	Running Slope	5-6%	10 ft	12	SF	\$120	<b>\$1,440</b>	
1353017	0.0 to 2.3 feet	Cross Slope (PAR)	2-3%	20 ft	46	SF	\$120	<b>\$5,520</b>	
1353004	16.3 to 17.3 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	

Funding Source: **TBD**

Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route	Year to be Completed				Priority
<b>S</b>	<b>1906050922</b>	<b>ROUTE 29</b>	<b>BUILDING 18</b>	<b>BUILDING 9</b>					<b>121.25</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1353005	28.6 to 29.6 feet	Vertical Change	.4	20 ft	20	LF	\$75	\$1,500	
1353006	34.8 to 35.8 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353007	41.0 to 42.0 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353008	47.1 to 48.1 feet	Vertical Change	.4	20 ft	20	LF	\$75	\$1,500	
1353009	65.7 to 66.7 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353010	90.3 to 91.3 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353011	96.4 to 97.4 feet	Vertical Change	.5	20 ft	20	LF	\$75	\$1,500	
1353012	158.3 to 159.3 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353013	166.6 to 167.6 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353014	170.7 to 171.7 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353018	177.6 to 180.2 feet	Cross Slope (PAR)	2-3%	20 ft	52	SF	\$120	\$6,240	
1353019	180.4 to 181.7 feet	Cross Slope (PAR)	3-4%	20 ft	26	SF	\$120	\$3,120	
1353020	185.1 to 186.6 feet	Cross Slope (PAR)	3-4%	20 ft	30	SF	\$120	\$3,600	
1353021	186.8 to 189.3 feet	Cross Slope (PAR)	3-4%	20 ft	50	SF	\$120	\$6,000	
1353022	190.7 to 192.8 feet	Cross Slope (PAR)	3-4%	20 ft	42	SF	\$120	\$5,040	
1353015	191.3 to 192.3 feet	Vertical Change	.3	20 ft	20	REF			
1353023	193.2 to 194.4 feet	Cross Slope (PAR)	3-4%	20 ft	24	SF	\$120	\$2,880	
1353024	194.4 to 196.2 feet	Cross Slope (PAR)	2-3%	20 ft	36	SF	\$120	\$4,320	
1353016	215.9 to 216.9 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353025	224.3 to 225.3 feet	Running Slope	5-6%	20 ft	20	SF	\$120	\$2,400	
1353026	225.3 to 228.6 feet	Running Slope	6-7%	20 ft	66	SF	\$120	\$7,920	
1352984	0.0 to 3.7 feet	Cross Slope (PAR)	3-4%	10 ft	37	SF	\$120	\$4,440	
1352995	18.1 to 20.6 feet	Running Slope	5-6%	10 ft	25	SF	\$120	\$3,000	
1352996	20.8 to 22.3 feet	Running Slope	5-6%	10 ft	15	SF	\$120	\$1,800	
1352997	31.9 to 35.4 feet	Running Slope	5-6%	10 ft	35	SF	\$120	\$4,200	
1352985	39.6 to 43.3 feet	Cross Slope (PAR)	4-5%	10 ft	37	SF	\$120	\$4,440	
1352986	43.8 to 46.3 feet	Cross Slope (PAR)	3-4%	10 ft	25	SF	\$120	\$3,000	
1352987	46.9 to 49.7 feet	Cross Slope (PAR)	2-3%	10 ft	28	SF	\$120	\$3,360	

Funding Source: **TBD**Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route					Priority
<b>W</b>	<b>1906050916</b>	<b>ROUTE 30</b>	<b>BUILDING 16</b>	<b>BUILDING 16</b>					<b>130</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1352988	49.8 to 52.0 feet	Cross Slope (PAR)	2-3%	10 ft	22	SF	\$120	<b>\$2,640</b>	
1352998	50.2 to 51.3 feet	Running Slope	7-8%	10 ft	11	REF			
1352989	54.6 to 55.7 feet	Cross Slope (PAR)	8-9%	10 ft	11	SF	\$120	<b>\$1,320</b>	
1352990	57.8 to 60.5 feet	Cross Slope (PAR)	5-6%	10 ft	27	SF	\$120	<b>\$3,240</b>	
1352991	60.8 to 68.0 feet	Cross Slope (PAR)	5-6%	10 ft	72	SF	\$120	<b>\$8,640</b>	
1352992	69.8 to 74.4 feet	Cross Slope (PAR)	3-4%	10 ft	46	SF	\$120	<b>\$5,520</b>	
1352993	74.4 to 76.7 feet	Cross Slope (PAR)	2-3%	10 ft	23	SF	\$120	<b>\$2,760</b>	
1352994	79.2 to 80.3 feet	Cross Slope (PAR)	2-3%	10 ft	11	SF	\$120	<b>\$1,320</b>	
1352983	10.8 to 12.0 feet	Cross Slope (PAR)	2-3%	10 ft	12	SF	\$120	<b>\$1,440</b>	
1352908	0.0 to 2.8 feet	Running Slope	10-11%	5 ft	14	SF	\$120	<b>\$1,680</b>	
1352909	2.8 to 5.9 feet	Running Slope	8-9%	5 ft	16	SF	\$120	<b>\$1,860</b>	
1352910	5.9 to 7.8 feet	Running Slope	6-7%	5 ft	10	REF			
1352862	7.7 to 12.7 feet	Cross Slope (PAR)	2-3%	5 ft	25	SF	\$120	<b>\$3,000</b>	
1352911	7.8 to 11.3 feet	Running Slope	5-6%	5 ft	18	REF			
1352912	11.6 to 13.4 feet	Running Slope	5-6%	5 ft	9	REF			
1352863	12.8 to 14.5 feet	Cross Slope (PAR)	3-4%	5 ft	9	SF	\$120	<b>\$1,020</b>	
1352913	14.1 to 16.8 feet	Running Slope	5-6%	5 ft	14	REF			
1352864	14.5 to 17.3 feet	Cross Slope (PAR)	2-3%	5 ft	14	SF	\$120	<b>\$1,680</b>	
1352865	18.9 to 22.3 feet	Cross Slope (PAR)	2-3%	5 ft	17	SF	\$120	<b>\$2,040</b>	
1352866	30.0 to 33.7 feet	Cross Slope (PAR)	2-3%	5 ft	19	SF	\$120	<b>\$2,220</b>	
1352867	35.0 to 37.7 feet	Cross Slope (PAR)	2-3%	5 ft	14	SF	\$120	<b>\$1,620</b>	
1352868	39.6 to 42.8 feet	Cross Slope (PAR)	3-4%	5 ft	16	SF	\$120	<b>\$1,920</b>	
1352869	43.4 to 49.4 feet	Cross Slope (PAR)	3-4%	5 ft	30	SF	\$120	<b>\$3,600</b>	
1352870	49.7 to 51.2 feet	Cross Slope (PAR)	4-5%	5 ft	8	SF	\$120	<b>\$900</b>	
1352871	51.7 to 53.4 feet	Cross Slope (PAR)	4-5%	5 ft	9	SF	\$120	<b>\$1,020</b>	
1352872	53.6 to 56.7 feet	Cross Slope (PAR)	5-6%	5 ft	16	SF	\$120	<b>\$1,860</b>	
1352873	56.8 to 58.2 feet	Cross Slope (PAR)	5-6%	5 ft	7	SF	\$120	<b>\$840</b>	
1352874	58.3 to 61.3 feet	Cross Slope (PAR)	5-6%	5 ft	15	SF	\$120	<b>\$1,800</b>	

Funding Source: **TBD**

Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route					Priority
<b>NE</b>	<b>1906050854</b>	<b>ROUTE 35</b>	<b>LOT 10</b>	<b>LOT 8</b>					<b>132.5</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1352875	64.8 to 66.1 feet	Cross Slope (PAR)	7-8%	5 ft	6	SF	\$120	<b>\$780</b>	
1352876	66.6 to 68.4 feet	Cross Slope (PAR)	7-8%	5 ft	9	SF	\$120	<b>\$1,080</b>	
1352877	68.8 to 70.0 feet	Cross Slope (PAR)	6-7%	5 ft	6	SF	\$120	<b>\$720</b>	
1352878	70.0 to 72.4 feet	Cross Slope (PAR)	5-6%	5 ft	12	SF	\$120	<b>\$1,440</b>	
1352879	75.4 to 78.5 feet	Cross Slope (PAR)	5-6%	5 ft	15	SF	\$120	<b>\$1,860</b>	
1352880	79.1 to 80.3 feet	Cross Slope (PAR)	4-5%	5 ft	6	SF	\$120	<b>\$720</b>	
1352881	100.6 to 102.5 feet	Cross Slope (PAR)	2-3%	5 ft	10	SF	\$120	<b>\$1,140</b>	
1352914	112.1 to 114.0 feet	Running Slope	5-6%	5 ft	10	SF	\$120	<b>\$1,140</b>	
1352882	133.3 to 134.3 feet	Cross Slope (PAR)	2-3%	5 ft	5	SF	\$120	<b>\$600</b>	
1352883	135.9 to 136.9 feet	Cross Slope (PAR)	2-3%	5 ft	5	SF	\$120	<b>\$600</b>	
1352884	141.3 to 143.0 feet	Cross Slope (PAR)	2-3%	5 ft	8	SF	\$120	<b>\$1,020</b>	
1352885	162.3 to 164.2 feet	Cross Slope (PAR)	2-3%	5 ft	9	SF	\$120	<b>\$1,140</b>	
1352886	164.5 to 166.4 feet	Cross Slope (PAR)	3-4%	5 ft	10	SF	\$120	<b>\$1,140</b>	
1352887	167.7 to 170.3 feet	Cross Slope (PAR)	3-4%	5 ft	13	SF	\$120	<b>\$1,560</b>	
1352888	170.4 to 174.4 feet	Cross Slope (PAR)	3-4%	5 ft	20	SF	\$120	<b>\$2,400</b>	
1352915	172.2 to 174.5 feet	Running Slope	5-6%	5 ft	12	REF			
1352889	175.2 to 176.8 feet	Cross Slope (PAR)	4-5%	5 ft	8	SF	\$120	<b>\$960</b>	
1352890	177.3 to 181.9 feet	Cross Slope (PAR)	3-4%	5 ft	23	SF	\$120	<b>\$2,760</b>	
1352916	181.3 to 184.6 feet	Running Slope	5-6%	5 ft	17	REF			
1352891	182.2 to 183.3 feet	Cross Slope (PAR)	3-4%	5 ft	6	SF	\$120	<b>\$660</b>	
1352892	183.3 to 184.5 feet	Cross Slope (PAR)	2-3%	5 ft	6	SF	\$120	<b>\$720</b>	
1352893	185.3 to 186.4 feet	Cross Slope (PAR)	3-4%	5 ft	6	SF	\$120	<b>\$660</b>	
1352917	185.5 to 186.9 feet	Running Slope	5-6%	5 ft	7	REF			
1352894	187.1 to 193.8 feet	Cross Slope (PAR)	4-5%	5 ft	34	SF	\$120	<b>\$4,020</b>	
1352895	194.0 to 196.7 feet	Cross Slope (PAR)	4-5%	5 ft	14	SF	\$120	<b>\$1,620</b>	
1352896	197.6 to 201.8 feet	Cross Slope (PAR)	4-5%	5 ft	21	SF	\$120	<b>\$2,520</b>	
1352897	201.9 to 205.3 feet	Cross Slope (PAR)	4-5%	5 ft	17	SF	\$120	<b>\$2,040</b>	
1352898	207.5 to 210.0 feet	Cross Slope (PAR)	4-5%	5 ft	13	SF	\$120	<b>\$1,500</b>	

Funding Source: **TBD**

Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route					Priority
<b>NE</b>	<b>1906050854</b>	<b>ROUTE 35</b>	<b>LOT 10</b>	<b>LOT 8</b>					<b>132.5</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1352918	208.6 to 209.6 feet	Running Slope	6-7%	5 ft	5	REF			
1352919	209.8 to 210.8 feet	Running Slope	6-7%	5 ft	5	REF			
1352899	212.0 to 213.3 feet	Cross Slope (PAR)	5-6%	5 ft	7	SF	\$120	<b>\$780</b>	
1352920	213.1 to 214.6 feet	Running Slope	5-6%	5 ft	8	REF			
1352900	215.3 to 219.3 feet	Cross Slope (PAR)	7-8%	5 ft	20	SF	\$120	<b>\$2,400</b>	
1352921	215.3 to 217.8 feet	Running Slope	5-6%	5 ft	13	REF			
1352922	220.0 to 223.8 feet	Running Slope	5-6%	5 ft	19	REF			
1352901	223.4 to 226.2 feet	Cross Slope (PAR)	6-7%	5 ft	14	SF	\$120	<b>\$1,680</b>	
1352923	224.7 to 226.1 feet	Running Slope	5-6%	5 ft	7	REF			
1352924	226.6 to 227.7 feet	Running Slope	5-6%	5 ft	6	REF			
1352902	227.1 to 228.1 feet	Cross Slope (PAR)	5-6%	5 ft	5	SF	\$120	<b>\$600</b>	
1352925	227.8 to 229.8 feet	Running Slope	5-6%	5 ft	10	REF			
1352903	228.2 to 230.8 feet	Cross Slope (PAR)	5-6%	5 ft	13	SF	\$120	<b>\$1,560</b>	
1352926	229.8 to 230.9 feet	Running Slope	6-7%	5 ft	6	REF			
1352927	231.8 to 233.3 feet	Running Slope	8-9%	5 ft	8	REF			
1352904	232.3 to 234.6 feet	Cross Slope (PAR)	4-5%	5 ft	12	SF	\$120	<b>\$1,380</b>	
1352928	235.0 to 236.0 feet	Running Slope	7-8%	5 ft	5	REF			
1352905	235.2 to 238.2 feet	Cross Slope (PAR)	4-5%	5 ft	15	SF	\$120	<b>\$1,800</b>	
1352929	236.7 to 238.1 feet	Running Slope	7-8%	5 ft	7	REF			
1352906	238.4 to 240.8 feet	Cross Slope (PAR)	3-4%	5 ft	12	SF	\$120	<b>\$1,440</b>	
1352930	238.8 to 241.4 feet	Running Slope	7-8%	5 ft	13	REF			
1352931	241.4 to 245.1 feet	Running Slope	9-10%	5 ft	19	REF			
1352907	241.8 to 243.8 feet	Cross Slope (PAR)	2-3%	5 ft	10	SF	\$120	<b>\$1,200</b>	
1352932	245.1 to 246.3 feet	Running Slope	7-8%	5 ft	6	SF	\$120	<b>\$720</b>	
1352933	247.1 to 250.3 feet	Running Slope	7-8%	5 ft	16	SF	\$120	<b>\$1,920</b>	
1352934	251.2 to 257.3 feet	Running Slope	7-8%	5 ft	31	SF	\$120	<b>\$3,660</b>	
1352935	259.2 to 260.3 feet	Running Slope	6-7%	5 ft	6	SF	\$120	<b>\$660</b>	
1352936	260.6 to 262.1 feet	Running Slope	6-7%	5 ft	8	SF	\$120	<b>\$900</b>	

Funding Source: **TBD**Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route					Priority
<b>NE</b>	<b>1906050854</b>	<b>ROUTE 35</b>	<b>LOT 10</b>	<b>LOT 8</b>					<b>132.5</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1352937	262.1 to 264.1 feet	Running Slope	5-6%	5 ft	10	SF	\$120	<b>\$1,200</b>	
1352938	270.5 to 273.2 feet	Running Slope	5-6%	5 ft	14	SF	\$120	<b>\$1,620</b>	
1352707	1.2 to 3.6 feet	Cross Slope (PAR)	3-4%	5 ft	12	SF	\$120	<b>\$1,440</b>	
1352708	3.6 to 12.8 feet	Cross Slope (PAR)	2-3%	5 ft	46	SF	\$120	<b>\$5,520</b>	
1352705	6.6 to 7.6 feet	<b>Vertical Change</b>	.3	5 ft	5	REF			
1352709	14.5 to 16.7 feet	Cross Slope (PAR)	3-4%	5 ft	11	SF	\$120	<b>\$1,320</b>	
1352710	16.7 to 23.6 feet	Cross Slope (PAR)	2-3%	5 ft	35	SF	\$120	<b>\$4,140</b>	
1352711	23.8 to 27.1 feet	Cross Slope (PAR)	3-4%	5 ft	17	SF	\$120	<b>\$1,980</b>	
1352712	27.3 to 30.8 feet	Cross Slope (PAR)	3-4%	5 ft	18	SF	\$120	<b>\$2,100</b>	
1352713	31.0 to 32.7 feet	Cross Slope (PAR)	2-3%	5 ft	9	SF	\$120	<b>\$1,020</b>	
1352714	33.7 to 36.1 feet	Cross Slope (PAR)	2-3%	5 ft	12	SF	\$120	<b>\$1,440</b>	
1352715	36.2 to 40.1 feet	Cross Slope (PAR)	3-4%	5 ft	19	SF	\$120	<b>\$2,340</b>	
1352716	40.8 to 42.9 feet	Cross Slope (PAR)	2-3%	5 ft	11	SF	\$120	<b>\$1,260</b>	
1352717	52.3 to 53.3 feet	Cross Slope (PAR)	2-3%	5 ft	5	SF	\$120	<b>\$600</b>	
1352718	53.5 to 59.8 feet	Cross Slope (PAR)	3-4%	5 ft	32	SF	\$120	<b>\$3,780</b>	
1352706	58.5 to 59.5 feet	<b>Vertical Change</b>	.3	5 ft	5	REF			
1352721	4.9 to 5.9 feet	<b>Vertical Change</b>	.4	8 ft	8	REF			
1352722	5.3 to 8.8 feet	Cross Slope (PAR)	2-3%	8 ft	28	SF	\$120	<b>\$3,360</b>	
1352723	8.9 to 10.4 feet	Cross Slope (PAR)	2-3%	8 ft	12	SF	\$120	<b>\$1,440</b>	
1352684	1.3 to 2.8 feet	Cross Slope (PAR)	2-3%	5 ft	8	SF	\$120	<b>\$900</b>	
1352685	2.9 to 5.2 feet	Cross Slope (PAR)	2-3%	5 ft	12	SF	\$120	<b>\$1,380</b>	
1352686	4.0 to 6.4 feet	Cross Slope (PAR)	2-3%	5 ft	12	SF	\$120	<b>\$1,440</b>	
1352687	5.8 to 8.7 feet	Cross Slope (PAR)	3-4%	5 ft	14	SF	\$120	<b>\$1,740</b>	
1352688	7.5 to 9.3 feet	Cross Slope (PAR)	2-3%	5 ft	9	SF	\$120	<b>\$1,080</b>	
1352689	8.8 to 10.7 feet	Cross Slope (PAR)	3-4%	5 ft	9	SF	\$120	<b>\$1,140</b>	
1352690	10.6 to 11.6 feet	Cross Slope (PAR)	2-3%	5 ft	5	SF	\$120	<b>\$600</b>	
1352691	11.3 to 12.8 feet	Cross Slope (PAR)	2-3%	5 ft	8	SF	\$120	<b>\$900</b>	
1352692	12.5 to 13.8 feet	Cross Slope (PAR)	2-3%	5 ft	7	SF	\$120	<b>\$780</b>	

Funding Source: **TBD**Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route	Year to be Completed				Priority
<b>W</b>	<b>1906050745</b>	<b>ROUTE 52</b>	<b>LOT 1</b>	<b>LOT 1</b>					<b>117.25</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1352703	15.5 to 18.0 feet	Running Slope	5-6%	5 ft	13	SF	\$120	<b>\$1,500</b>	
1352704	19.7 to 21.7 feet	Running Slope	7-8%	5 ft	10	SF	\$120	<b>\$1,200</b>	
1352681	31.7 to 32.7 feet	<b>Vertical Change</b>	.3	5 ft	5	LF	\$75	<b>\$375</b>	
1352682	41.2 to 42.2 feet	<b>Vertical Change</b>	.3	5 ft	5	REF			
1352693	41.6 to 42.7 feet	Cross Slope (PAR)	2-3%	5 ft	6	SF	\$120	<b>\$660</b>	
1352694	42.9 to 44.0 feet	Cross Slope (PAR)	2-3%	5 ft	6	SF	\$120	<b>\$660</b>	
1352695	54.0 to 56.0 feet	Cross Slope (PAR)	2-3%	5 ft	10	SF	\$120	<b>\$1,200</b>	
1352696	56.4 to 60.2 feet	Cross Slope (PAR)	2-3%	5 ft	19	SF	\$120	<b>\$2,280</b>	
1352697	59.9 to 62.1 feet	Cross Slope (PAR)	2-3%	5 ft	11	SF	\$120	<b>\$1,320</b>	
1352698	60.3 to 64.9 feet	Cross Slope (PAR)	3-4%	5 ft	23	SF	\$120	<b>\$2,760</b>	
1352699	62.1 to 63.6 feet	Cross Slope (PAR)	3-4%	5 ft	8	SF	\$120	<b>\$900</b>	
1352700	63.6 to 65.8 feet	Cross Slope (PAR)	2-3%	5 ft	11	SF	\$120	<b>\$1,320</b>	
1352683	64.3 to 68.7 feet	<b>Vertical Change</b>	.3	5 ft	22	REF			
1352701	64.9 to 67.0 feet	Cross Slope (PAR)	2-3%	5 ft	10	SF	\$120	<b>\$1,260</b>	
1352702	67.8 to 72.2 feet	Cross Slope (PAR)	2-3%	5 ft	22	SF	\$120	<b>\$2,640</b>	
1352719	3.3 to 6.5 feet	<b>Vertical Change</b>	.3	5 ft	16	LF	\$75	<b>\$1,200</b>	
1352720	7.8 to 10.3 feet	Running Slope	7-8%	5 ft	13	SF	\$120	<b>\$1,500</b>	
1353049	17.6 to 18.6 feet	<b>Vertical Change</b>	.4	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353050	37.2 to 38.2 feet	<b>Vertical Change</b>	.4	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353051	120.6 to 121.6 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353053	0.0 to 3.2 feet	Cross Slope (PAR)	2-3%	20 ft	64	SF	\$120	<b>\$7,680</b>	
1353054	3.3 to 5.6 feet	Cross Slope (PAR)	2-3%	20 ft	46	SF	\$120	<b>\$5,520</b>	
1353055	6.2 to 7.5 feet	Cross Slope (PAR)	2-3%	20 ft	26	SF	\$120	<b>\$3,120</b>	
1353052	75.3 to 80.6 feet	<b>Vertical Change</b>	.3	20 ft	106	LF	\$75	<b>\$7,950</b>	
1353056	61.3 to 62.3 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353058	76.9 to 78.0 feet	Cross Slope (PAR)	2-3%	20 ft	22	SF	\$120	<b>\$2,640</b>	
1353057	105.6 to 106.6 feet	<b>Vertical Change</b>	.6	20 ft	20	LF	\$75	<b>\$1,500</b>	
1353059	9.4 to 10.4 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	

Funding Source: TBD

Year to be Completed TBD

Direction Traveled	Run ID	Route	Start of Route	End of Route					Priority
<b>E</b>	<b>1908130740</b>	<b>ROUTE 60</b>	<b>BUILDING 3</b>	<b>BUILDING 3</b>					<b>121.25</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1353060	17.7 to 18.7 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353066	34.1 to 36.1 feet	Cross Slope (PAR)	2-3%	20 ft	40	SF	\$120	\$4,800	
1353067	53.6 to 66.0 feet	Cross Slope (PAR)	2-3%	20 ft	248	SF	\$120	\$29,760	
1353061	56.6 to 57.6 feet	Vertical Change	.3	20 ft	20	REF			
1353062	63.3 to 64.3 feet	Vertical Change	.4	20 ft	20	REF			
1353068	73.8 to 79.1 feet	Cross Slope (PAR)	2-3%	20 ft	106	SF	\$120	\$12,720	
1353070	74.5 to 75.8 feet	Running Slope	6-7%	20 ft	26	REF			
1353071	75.8 to 77.3 feet	Running Slope	5-6%	20 ft	30	REF			
1353063	76.4 to 77.4 feet	Vertical Change	.3	20 ft	20	REF			
1353069	82.8 to 87.1 feet	Cross Slope (PAR)	3-4%	20 ft	86	SF	\$120	\$10,320	
1353064	84.7 to 85.7 feet	Vertical Change	.3	20 ft	20	REF			
1353065	121.7 to 122.7 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353079	0.0 to 2.3 feet	Running Slope	6-7%	8 ft	18	REF			
1353072	0.8 to 1.8 feet	Vertical Change	.3	8 ft	8	REF			
1353075	0.8 to 4.1 feet	Cross Slope (PAR)	3-4%	8 ft	26	SF	\$120	\$3,168	
1353080	2.3 to 4.3 feet	Running Slope	5-6%	8 ft	16	REF			
1353076	4.3 to 11.3 feet	Cross Slope (PAR)	2-3%	8 ft	56	SF	\$120	\$6,720	
1353077	64.5 to 67.1 feet	Cross Slope (PAR)	2-3%	8 ft	21	SF	\$120	\$2,496	
1353073	71.8 to 72.8 feet	Vertical Change	.4	8 ft	8	LF	\$75	\$600	
1353074	79.0 to 80.0 feet	Vertical Change	.5	8 ft	8	LF	\$75	\$600	
1353078	104.2 to 105.3 feet	Cross Slope (PAR)	2-3%	8 ft	9	SF	\$120	\$1,056	
1353081	3.4 to 4.4 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353082	6.5 to 7.5 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353083	9.7 to 10.7 feet	Vertical Change	.4	20 ft	20	LF	\$75	\$1,500	
1353084	15.9 to 16.9 feet	Vertical Change	.5	20 ft	20	LF	\$75	\$1,500	
1353085	22.0 to 26.0 feet	Vertical Change	.3	20 ft	80	LF	\$75	\$6,000	
1353108	43.3 to 44.4 feet	Cross Slope (PAR)	2-3%	20 ft	22	SF	\$120	\$2,640	
1353109	45.0 to 46.9 feet	Cross Slope (PAR)	2-3%	20 ft	38	SF	\$120	\$4,560	



Funding Source: **TBD**Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route	Year to be Completed				Priority
<b>W / N</b>	<b>1908130750</b>	<b>ROUTE 62</b>	<b>BUILDING 18</b>	<b>LOT 9</b>					<b>120</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1353110	50.1 to 53.4 feet	Cross Slope (PAR)	2-3%	20 ft	66	SF	\$120	<b>\$7,920</b>	
1353086	53.1 to 54.1 feet	<b>Vertical Change</b>	.4	20 ft	20	REF			
1353111	53.5 to 57.3 feet	Cross Slope (PAR)	2-3%	20 ft	76	SF	\$120	<b>\$9,120</b>	
1353087	56.2 to 57.2 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1353112	57.4 to 59.5 feet	Cross Slope (PAR)	3-4%	20 ft	42	SF	\$120	<b>\$5,040</b>	
1353113	59.5 to 68.1 feet	Cross Slope (PAR)	2-3%	20 ft	172	SF	\$120	<b>\$20,640</b>	
1353114	71.9 to 75.3 feet	Cross Slope (PAR)	2-3%	20 ft	68	SF	\$120	<b>\$8,160</b>	
1353115	77.2 to 80.5 feet	Cross Slope (PAR)	2-3%	20 ft	66	SF	\$120	<b>\$7,920</b>	
1353088	77.7 to 78.7 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1353089	83.9 to 84.9 feet	<b>Vertical Change</b>	.4	20 ft	20	REF			
1353116	84.3 to 85.8 feet	Cross Slope (PAR)	2-3%	20 ft	30	SF	\$120	<b>\$3,600</b>	
1353090	96.2 to 97.2 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1353117	96.4 to 100.3 feet	Cross Slope (PAR)	2-3%	20 ft	78	SF	\$120	<b>\$9,360</b>	
1353118	107.1 to 112.5 feet	Cross Slope (PAR)	2-3%	20 ft	108	SF	\$120	<b>\$12,960</b>	
1353119	113.0 to 116.4 feet	Cross Slope (PAR)	2-3%	20 ft	68	SF	\$120	<b>\$8,160</b>	
1353120	117.5 to 120.8 feet	Cross Slope (PAR)	3-4%	20 ft	66	SF	\$120	<b>\$7,920</b>	
1353091	119.7 to 120.7 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1353092	119.7 to 120.7 feet	<b>Vertical Change</b>	0	20 ft	20	REF			
1353093	124.4 to 125.4 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1353121	125.3 to 128.2 feet	Cross Slope (PAR)	2-3%	20 ft	58	SF	\$120	<b>\$6,960</b>	
1353122	130.2 to 135.2 feet	Cross Slope (PAR)	2-3%	20 ft	100	SF	\$120	<b>\$12,000</b>	
1353094	135.6 to 136.6 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1353123	135.8 to 138.0 feet	Cross Slope (PAR)	2-3%	20 ft	44	SF	\$120	<b>\$5,280</b>	
1353124	138.6 to 143.2 feet	Cross Slope (PAR)	2-3%	20 ft	92	SF	\$120	<b>\$11,040</b>	
1353125	146.3 to 151.6 feet	Cross Slope (PAR)	2-3%	20 ft	106	SF	\$120	<b>\$12,720</b>	
1353095	150.3 to 151.3 feet	<b>Vertical Change</b>	.3	20 ft	20	REF			
1353126	153.3 to 158.8 feet	Cross Slope (PAR)	2-3%	20 ft	110	SF	\$120	<b>\$13,200</b>	
1353127	160.8 to 165.3 feet	Cross Slope (PAR)	2-3%	20 ft	90	SF	\$120	<b>\$10,800</b>	

Funding Source: **TBD**Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route	Year to be Completed <b>TBD</b>					Priority
<b>W / N</b>	<b>1908130750</b>	<b>ROUTE 62</b>	<b>BUILDING 18</b>	<b>LOT 9</b>						<b>120</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total		
1353128	166.6 to 168.2 feet	Cross Slope (PAR)	3-4%	20 ft	32	SF	\$120	<b>\$3,840</b>		
1353129	169.3 to 171.3 feet	Cross Slope (PAR)	2-3%	20 ft	40	SF	\$120	<b>\$4,800</b>		
1353096	175.3 to 176.3 feet	<b>Vertical Change</b>	.3	20 ft	20	REF				
1353130	175.4 to 178.7 feet	Cross Slope (PAR)	2-3%	20 ft	66	SF	\$120	<b>\$7,920</b>		
1353097	187.6 to 188.6 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>		
1353098	212.4 to 213.4 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>		
1353099	267.9 to 268.9 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>		
1353131	269.6 to 271.1 feet	Cross Slope (PAR)	2-3%	20 ft	30	SF	\$120	<b>\$3,600</b>		
1353132	271.2 to 272.7 feet	Cross Slope (PAR)	2-3%	20 ft	30	SF	\$120	<b>\$3,600</b>		
1353133	272.8 to 274.9 feet	Cross Slope (PAR)	2-3%	20 ft	42	SF	\$120	<b>\$5,040</b>		
1353100	279.2 to 280.2 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>		
1353101	287.7 to 288.7 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>		
1353102	292.8 to 293.8 feet	<b>Vertical Change</b>	.3	20 ft	20	REF				
1353134	293.4 to 294.9 feet	Cross Slope (PAR)	2-3%	20 ft	30	SF	\$120	<b>\$3,600</b>		
1353135	295.3 to 300.0 feet	Cross Slope (PAR)	3-4%	20 ft	94	SF	\$120	<b>\$11,280</b>		
1353103	300.8 to 301.8 feet	<b>Vertical Change</b>	.3	20 ft	20	REF				
1353136	300.8 to 302.1 feet	Cross Slope (PAR)	3-4%	20 ft	26	SF	\$120	<b>\$3,120</b>		
1353137	304.3 to 306.3 feet	Cross Slope (PAR)	2-3%	20 ft	40	SF	\$120	<b>\$4,800</b>		
1353138	306.4 to 307.5 feet	Cross Slope (PAR)	2-3%	20 ft	22	SF	\$120	<b>\$2,640</b>		
1353139	315.6 to 320.3 feet	Cross Slope (PAR)	2-3%	20 ft	94	SF	\$120	<b>\$11,280</b>		
1353104	325.6 to 326.6 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>		
1353105	331.8 to 332.8 feet	<b>Vertical Change</b>	.4	20 ft	20	LF	\$75	<b>\$1,500</b>		
1353106	338.0 to 339.0 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>		
1353140	343.4 to 347.5 feet	Cross Slope (PAR)	2-3%	20 ft	82	SF	\$120	<b>\$9,840</b>		
1353141	347.6 to 348.8 feet	Cross Slope (PAR)	3-4%	20 ft	24	SF	\$120	<b>\$2,880</b>		
1353107	350.5 to 351.5 feet	<b>Vertical Change</b>	.3	20 ft	20	REF				
1353142	351.5 to 352.8 feet	Cross Slope (PAR)	2-3%	20 ft	26	SF	\$120	<b>\$3,120</b>		
1353143	2.1 to 3.1 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>		

Funding Source: TBD

Year to be Completed TBD

Direction Traveled	Run ID	Route	Start of Route	End of Route					Priority
<b>E</b>	<b>1908130752</b>	<b>ROUTE 63</b>	<b>BUILDING 22</b>	<b>BUILDING 22</b>					<b>110</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1353144	5.2 to 6.2 feet	Vertical Change	.4	20 ft	20	LF	\$75	\$1,500	
1353145	14.4 to 15.4 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353146	17.5 to 18.5 feet	Vertical Change	.5	20 ft	20	LF	\$75	\$1,500	
1353147	20.6 to 21.6 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353148	36.1 to 37.1 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353149	45.3 to 46.3 feet	Vertical Change	.4	20 ft	20	LF	\$75	\$1,500	
1353162	4.9 to 7.0 feet	Cross Slope (PAR)	2-3%	20 ft	42	SF	\$120	\$5,040	
1353163	7.6 to 8.8 feet	Cross Slope (PAR)	3-4%	20 ft	24	SF	\$120	\$2,880	
1353164	8.8 to 10.2 feet	Cross Slope (PAR)	2-3%	20 ft	28	SF	\$120	\$3,360	
1353150	17.5 to 18.5 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353151	32.5 to 33.5 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353165	33.9 to 37.3 feet	Cross Slope (PAR)	2-3%	20 ft	68	SF	\$120	\$8,160	
1353152	37.6 to 38.6 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353153	41.4 to 42.4 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353154	45.3 to 46.3 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353166	49.3 to 51.8 feet	Cross Slope (PAR)	2-3%	20 ft	50	SF	\$120	\$6,000	
1353167	54.5 to 56.0 feet	Cross Slope (PAR)	2-3%	20 ft	30	SF	\$120	\$3,600	
1353155	58.2 to 59.2 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353156	77.0 to 78.0 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353157	83.8 to 84.8 feet	Vertical Change	.4	20 ft	20	LF	\$75	\$1,500	
1353158	96.0 to 97.0 feet	Vertical Change	.4	20 ft	20	LF	\$75	\$1,500	
1353159	120.8 to 121.8 feet	Vertical Change	.4	20 ft	20	LF	\$75	\$1,500	
1353160	133.1 to 134.1 feet	Vertical Change	.4	20 ft	20	LF	\$75	\$1,500	
1353161	139.3 to 140.3 feet	Vertical Change	.3	20 ft	20	LF	\$75	\$1,500	
1353168	152.3 to 153.4 feet	Running Slope	5-6%	20 ft	22	SF	\$120	\$2,640	
1353176	0.4 to 3.7 feet	Running Slope	9-10%	6 ft	20	SF	\$120	\$2,376	
1353177	4.3 to 6.0 feet	Running Slope	8-9%	6 ft	10	REF			
1353170	4.7 to 6.4 feet	Cross Slope (PAR)	3-4%	6 ft	10	SF	\$120	\$1,224	

Funding Source: **TBD**Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route					Priority
<b>W</b>	<b>1908130806</b>	<b>ROUTE 65</b>	<b>BUILDING 18</b>	<b>BUILDING 18</b>					<b>116</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1353171	6.5 to 7.6 feet	Cross Slope (PAR)	3-4%	6 ft	7	SF	\$120	<b>\$792</b>	
1353172	8.2 to 11.2 feet	Cross Slope (PAR)	2-3%	6 ft	18	SF	\$120	<b>\$2,160</b>	
1353173	11.3 to 12.6 feet	Cross Slope (PAR)	3-4%	6 ft	8	SF	\$120	<b>\$936</b>	
1353174	13.5 to 14.5 feet	Cross Slope (PAR)	2-3%	6 ft	6	SF	\$120	<b>\$720</b>	
1353175	16.6 to 20.3 feet	Cross Slope (PAR)	2-3%	6 ft	22	SF	\$120	<b>\$2,664</b>	
1353169	50.4 to 51.4 feet	<b>Vertical Change</b>	.6	6 ft	6	SF	\$75	<b>\$450</b>	
1352724	83.2 to 84.2 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1352731	139.4 to 140.8 feet	Cross Slope (PAR)	2-3%	20 ft	28	SF	\$120	<b>\$3,360</b>	
1352732	146.6 to 148.2 feet	Cross Slope (PAR)	2-3%	20 ft	32	SF	\$120	<b>\$3,840</b>	
1352746	156.8 to 158.2 feet	Running Slope	5-6%	20 ft	28	SF	\$120	<b>\$3,360</b>	
1352733	158.3 to 159.8 feet	Cross Slope (PAR)	2-3%	20 ft	30	SF	\$120	<b>\$3,600</b>	
1352747	158.3 to 159.7 feet	Running Slope	5-6%	20 ft	28	REF			
1352734	165.9 to 167.2 feet	Cross Slope (PAR)	5-6%	20 ft	26	SF	\$120	<b>\$3,120</b>	
1352735	168.9 to 171.3 feet	Cross Slope (PAR)	4-5%	20 ft	48	SF	\$120	<b>\$5,760</b>	
1352736	173.1 to 175.7 feet	Cross Slope (PAR)	3-4%	20 ft	52	SF	\$120	<b>\$6,240</b>	
1352737	175.7 to 178.1 feet	Cross Slope (PAR)	2-3%	20 ft	48	SF	\$120	<b>\$5,760</b>	
1352748	179.5 to 180.8 feet	Running Slope	5-6%	20 ft	26	SF	\$120	<b>\$3,120</b>	
1352749	180.9 to 182.8 feet	Running Slope	5-6%	20 ft	38	SF	\$120	<b>\$4,560</b>	
1352725	182.4 to 183.4 feet	<b>Vertical Change</b>	.4	20 ft	20	LF	\$75	<b>\$1,500</b>	
1352750	183.0 to 184.3 feet	Running Slope	5-6%	20 ft	26	SF	\$120	<b>\$3,120</b>	
1352726	211.3 to 212.3 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1352738	277.5 to 279.1 feet	Cross Slope (PAR)	2-3%	20 ft	32	SF	\$120	<b>\$3,840</b>	
1352739	279.3 to 280.3 feet	Cross Slope (PAR)	3-4%	20 ft	20	SF	\$120	<b>\$2,400</b>	
1352727	281.2 to 282.2 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1352740	282.7 to 283.8 feet	Cross Slope (PAR)	3-4%	20 ft	22	SF	\$120	<b>\$2,640</b>	
1352741	284.2 to 289.2 feet	Cross Slope (PAR)	2-3%	20 ft	100	SF	\$120	<b>\$12,000</b>	
1352742	291.7 to 293.8 feet	Cross Slope (PAR)	2-3%	20 ft	42	SF	\$120	<b>\$5,040</b>	
1352728	306.1 to 307.1 feet	<b>Vertical Change</b>	.4	20 ft	20	LF	\$75	<b>\$1,500</b>	

Funding Source: **TBD**Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route					Priority
<b>NE /</b>	<b>1906050819</b>	<b>ROUTE 8</b>	<b>CAMPUS CIR</b>	<b>BUILDING 3</b>					<b>128.75</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1352729	340.5 to 341.5 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1352743	472.3 to 474.4 feet	Cross Slope (PAR)	2-3%	20 ft	42	SF	\$120	<b>\$5,040</b>	
1352744	475.1 to 476.8 feet	Cross Slope (PAR)	3-4%	20 ft	34	SF	\$120	<b>\$4,080</b>	
1352745	477.7 to 478.8 feet	Cross Slope (PAR)	4-5%	20 ft	22	SF	\$120	<b>\$2,640</b>	
1352730	480.5 to 481.5 feet	<b>Vertical Change</b>	.3	20 ft	20	LF	\$75	<b>\$1,500</b>	
1352969	8.0 to 10.9 feet	Cross Slope (PAR)	2-3%	10 ft	29	SF	\$120	<b>\$3,480</b>	
1352939	8.6 to 9.6 feet	<b>Vertical Change</b>	.4	10 ft	10	REF			
1352940	30.2 to 31.2 feet	<b>Vertical Change</b>	.4	10 ft	10	LF	\$75	<b>\$750</b>	
1352941	34.3 to 35.3 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352942	42.5 to 43.5 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352970	56.6 to 58.8 feet	Cross Slope (PAR)	2-3%	10 ft	22	SF	\$120	<b>\$2,640</b>	
1352971	58.9 to 60.7 feet	Cross Slope (PAR)	2-3%	10 ft	18	SF	\$120	<b>\$2,160</b>	
1352943	61.1 to 62.1 feet	<b>Vertical Change</b>	.4	10 ft	10	LF	\$75	<b>\$750</b>	
1352944	66.3 to 67.3 feet	<b>Vertical Change</b>	.4	10 ft	10	LF	\$75	<b>\$750</b>	
1352945	72.0 to 73.0 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352946	90.5 to 91.5 feet	<b>Vertical Change</b>	.3	10 ft	10	REF			
1352972	90.5 to 95.3 feet	Cross Slope (PAR)	2-3%	10 ft	48	SF	\$120	<b>\$5,760</b>	
1352973	95.5 to 99.0 feet	Cross Slope (PAR)	2-3%	10 ft	35	SF	\$120	<b>\$4,200</b>	
1352947	95.6 to 96.6 feet	<b>Vertical Change</b>	.3	10 ft	10	REF			
1352982	101.8 to 102.8 feet	Running Slope	5-6%	10 ft	10	SF	\$120	<b>\$1,200</b>	
1352948	105.4 to 106.4 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352949	152.2 to 153.2 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352950	164.5 to 165.5 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352974	183.0 to 185.3 feet	Cross Slope (PAR)	2-3%	10 ft	23	SF	\$120	<b>\$2,760</b>	
1352951	185.1 to 186.1 feet	<b>Vertical Change</b>	.3	10 ft	10	REF			
1352952	193.3 to 194.3 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352953	197.4 to 198.4 feet	<b>Vertical Change</b>	.4	10 ft	10	LF	\$75	<b>\$750</b>	
1352954	201.5 to 202.5 feet	<b>Vertical Change</b>	.4	10 ft	10	LF	\$75	<b>\$750</b>	

Funding Source: **TBD**Year to be Completed **TBD**

Direction Traveled	Run ID	Route	Start of Route	End of Route					Priority
<b>N</b>	<b>1906050911</b>	<b>ROUTE 9</b>	<b>BUILDING 9</b>	<b>BUILDING 16</b>					<b>128.75</b>
ID	Dist. from Route Start	Barrier Type	As-is Measurement/Notes	Sidewalk Width	Qty	Unit	Cost	Total	
1352955	226.2 to 227.2 feet	<b>Vertical Change</b>	.5	10 ft	10	LF	\$75	<b>\$750</b>	
1352956	242.7 to 243.7 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352975	253.6 to 254.6 feet	Cross Slope (PAR)	2-3%	10 ft	10	SF	\$120	<b>\$1,200</b>	
1352957	255.1 to 256.1 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352976	256.5 to 258.6 feet	Cross Slope (PAR)	5-6%	10 ft	21	SF	\$120	<b>\$2,520</b>	
1352977	260.8 to 261.8 feet	Cross Slope (PAR)	2-3%	10 ft	10	SF	\$120	<b>\$1,200</b>	
1352958	341.5 to 342.5 feet	<b>Vertical Change</b>	.4	10 ft	10	LF	\$75	<b>\$750</b>	
1352959	346.5 to 347.5 feet	<b>Vertical Change</b>	0	10 ft	10	LF	\$75	<b>\$750</b>	
1352960	346.6 to 347.6 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352961	355.1 to 356.1 feet	<b>Vertical Change</b>	.4	10 ft	10	REF			
1352978	356.1 to 357.9 feet	Cross Slope (PAR)	2-3%	10 ft	18	SF	\$120	<b>\$2,160</b>	
1352962	361.4 to 362.4 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352963	367.6 to 368.6 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352964	373.7 to 374.7 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352965	379.8 to 380.8 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352966	392.2 to 393.2 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	
1352967	404.8 to 408.0 feet	<b>Vertical Change</b>	.3	10 ft	32	LF	\$75	<b>\$2,400</b>	
1352979	408.2 to 410.4 feet	Cross Slope (PAR)	3-4%	10 ft	22	SF	\$120	<b>\$2,640</b>	
1352980	410.6 to 412.1 feet	Cross Slope (PAR)	2-3%	10 ft	15	SF	\$120	<b>\$1,800</b>	
1352981	418.7 to 420.2 feet	Cross Slope (PAR)	2-3%	10 ft	15	SF	\$120	<b>\$1,800</b>	
1352968	426.8 to 427.8 feet	<b>Vertical Change</b>	.3	10 ft	10	LF	\$75	<b>\$750</b>	

**Total Cost for College Sidewalks:****\$1,488,099.00**